



## FIRST FLOOR CHIMNEY REPAIR

**3/8"=1'-0"**

NOTE:

1. TEMPORARILY REMOVE THE METAL HOOD AND STEEL SHELF AND REINSTALL WHEN CHIMNEY RECONSTRUCTION IS COMPLETE.
2. NEEDLE AND SHORE EXIST. CHIMNEY ABOVE THE SECOND FLOOR AS SHOWN. REMOVE EXIST. CHIMNEY COMPLETELY BELOW SECOND FLOOR AND RECONSTRUCT ON A NEW CONCRETE FOOTING.

PHILIP PAUL, P.E.  
STRUCTURAL ENGINEER

FIVE WENZEL DR. • LAWRENCEVILLE, N.J. 08648 • 609-883-4569

**PERMANENT REPAIR DETAILS  
FOR THE OLD MILLSTONE FORGE  
NORTH RIVER STREET  
MILLSTONE, NEW JERSEY**

PR-6.00